The Netherlands Minewater BV



General

Owner

Region

Municipality of Heerlen Limburg, south region of the Netherlands

Operator

Minewater BV

Project

Inhabitants connected

125.000 m2 connected. 175.000 m2 contracted, will be connected

Design of the DH

By technical team minewater by

Installed geothermal capacity

10 Megawatt

Production of heating and/or cooling

both

1. mid 2007 – mid

Others uses (drinking water, cascade uses...) Dates of beginning and end of construction

2008 (large backbone) 2. end 2012 finalized mid 2013 (on clusterlevel)

Planning of the operation (from pre-studies to full completion)

completed

Organisational scheme

_

Administration scheme

-

Difficulties faced

Geological uncertainties Unequal level playing field with fossil fuels Cost mitigation

Administrative permits

3 and 1 pending (under Heat Act)

Comparison with fossil energies

Problematic!

Financing

Investment for geothermal well

€ 5,5 mio Shallow geothermal in mine. Investment for geothermal heating station

€ 1,5 mio

Investment for DH network and

Financing (banks, funds,

Municipality of Heerlen and funding

substation	€8 mio	PPP)	programmes
Cost of the produced MWh Final energy cost	€ 6,8 /Gj	Cost of the MWh sold Taxes	In between € 18- €
Pay back	50 years for infrastructure 20 years installation	Amount of Subsidies if any	25/GJ incl VAT 50%

Technical

Installed capacity (MWth)	Heat 4MWth Cold 8MWth	subsurface and surface technical schemes	Cluster developement		
Operating		Temperature of the	Production 28		
Temperature of	Low temperature 28	geothermal	degrees		
the DH	degrees Celsius heat	resource	Injection 18 degrees		
	16 degrees Celsius	(production -	Production cold 16		
	cold	injection)	degrees		
			Injection 24 degrees		
Geothermal flow		Heat Pump			
rate	Heat 240 m3/hour	if any	COP heating 5-7		
	Cold 480 m3/hour	(power in Mwe and	COP cooling 4-6		
		COP)			
Innovation if any	Development to dh	Engineering			
	smart grid				
DH Length (m)	8 kilometer				